

REFERENCE OF TENDER	DESCRIPTION OF TENDER	TIME PERIOD OF TENDER	DEPARTMENT/DIVISION/ UNIT REQUESTING TENDER	FEES	CLOSING DATE NOT LATER THAN 2.00PM	FOCAL PERSON
KK/12/2023/JPK	<p>FABRICATION OF NEW RC TRENCH, REPLACEMENT OF NEW CHWP AND HVAC DUCTING REPAIR AND DEEP CLEANING AT BERAKAS HEALTH CENTRE</p> <p><u>Eligibility For Tenderers:</u> Registered with Ministry of Health Or and Ministry of Development</p> <p><u>Class:</u> I, II and above</p> <p><u>Category:</u> A01, B01, M01 &amp; KPB04</p>	-	DEPARTMENT OF HEALTH SERVICES	\$30.00	31 <sup>ST</sup> JANUARY 2023	<p>Zafiratul Adawiyah binti Abd Azim Chong Ketua Bhg Pemeliharaan Estet Brunei Muara dan Pusat-Pusat Kesihatan Ministry of Health Negara Brunei Darussalam Contact No.: 2332768 e-mail: <a href="mailto:community.health@moh.gov.bn">community.health@moh.gov.bn</a></p>

## SECTION 2

### SPECIFICATIONS AND REQUIREMENTS

TENDER REFERENCE NO: KK/12/2023/JPK

INVITATION TO TENDER  
FABRICATION OF NEW RC TRENCH, REPLACEMENT OF NEW CHWP AND HVAC DUCTING  
REPAIR AND DEEP CLEANING, AT BERAKAS HEALTH CENTRE

ITEM NO.	DESCRIPTION	QTY	UNIT
	<b>NOTE:</b> <ol style="list-style-type: none"><li>1. Contractor is advice to <b>visit the site and fill in the Site visit form as per attach</b> prior to tender price.</li><li>2. Supply all labour, materials, tools, equipment, PPE and transport for the proper execution of the following works to its proper working conditions as directed and to S.O. satisfaction.</li><li>3. Rate shall include to make good all works disturb to match or as directed by S.O and to remove debris to Contractor's own dumping Yard.</li><li>4. No claims for additional payment will be entertained as the grounds of misunderstanding or misinterpretation of site condition, measurements etc.</li><li>5. Contractor / vendor <b>MUST</b> be stated the brand offer and <b>ATTACH</b> catalog brand.</li><li>6. Contractor / vendor <b>MUST</b> submit work programme.</li></ol>		
<b>1.0</b>	<b>MOBILIZATION, HACKING, &amp; FABRICATION WORK:</b>		
<b>1.1</b>	Mobilization of excavator machine on site.	Lump	Sum
<b>1.2</b>	Hacking and cutting the road concrete by using cutting machine. The works shall include rectification works and make good unforeseen services pipe.	Lump	Sum
<b>1.3</b>	Excavation work of Top soil with approximate measurement 1m (W) x 0.40m (D). (Approximate Length – 150m). The works shall include rectification works and make good unforeseen services pipe.	1	Lot
<b>1.4</b>	Fabrication of form work and timber framing(W) x 0.40m (D) x 150m (L)).	1	Lot
<b>1.5</b>	Lay PVC sheet and BRC along the trench area.	1	Lot
<b>1.6</b>	Lay Ready mix concrete G30.	Lump	Sum
<b>2.0</b>	<b>METAL COVER:</b>		
<b>2.1</b>	Fabricate and install with heavy duty metal cover for road crossing. (Approximate measurement – 1m (W) x 9.0m (L)).	Lump	sum
<b>2.2</b>	Fabricate and install with metal cover for field area. (Approximate measurement (W) x (L) – 1.0m x 11m – 1m x 17m – 0.75m x 23m – 0.50m x 45m – 0.30m x 37m).	Lump	sum

ITEM NO.	DESCRIPTION	QTY	UNIT
3.0	<b>NEW CHILL WATER PIPE c/w INSULATION CHEMICAL:</b>		
3.1	Supply, Lay and install with new pre-insulated carbon steel piping (Carbon steel pipe 6" and Carbon steel pipe 4") including elbows, tees, reducer, and other necessary material associated with the work required. The work shall include hacking works, modification works, connection of the new CHWP with the existing system: Ensure during the by-pass connectivity of the piping system there is no disturbance of the air conditioning system inside the building as per S.O approval.	1	Lot
3.2	Supply and install with new insulation chemical at the CHWP including pressure testing, flushing out and refill fresh water.	Lump	sum
4.0	<b>UV-C AIR DUCT STERILIZER:</b>		
4.1	Supply and install with new UV-C AIR DUCT STERILIZER including lamp, Ballast and mounting bracket for HVAC air germicidal Disinfection and sterilization. The work shall include wiring works 2.5mm connected to the nearest Distribution board, conduit connection, PVC pipes and new MCB.  (Brand: .....)	16	No
	<p><b>This Package are included:</b></p> <ul style="list-style-type: none"> <li>- <b>Restoration of defaulted ducting only works in building and thermal deep cleaning sanitization to ALL HVAC ducting system in the building.</b></li> <li>- <b>Ensure all the system running properly after the connectivity.</b></li> <li>- <b>3 years Warranty for CHWP and trenching works including maintenance.</b></li> <li>- <b>1-year Warranty for Ducting replacement.</b></li> <li>- <b>5-year Warranty for UV light.</b></li> </ul>		

## SECTION 3

### TENDER FORM

TENDER REFERENCE NO: KK/12/2023/JPK

**INVITATION TO TENDER  
FABRICATION OF NEW RC TRENCH, REPLACEMENT OF NEW CHWP AND HVAC DUCTING  
REPAIR AND DEEP CLEANING AT BERAKAS HEALTH CENTRE**

ITEM NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT	
					\$	¢
	<p><b>NOTE:</b></p> <ol style="list-style-type: none"> <li>1. Contractor is advice to <b>visit the site and fill in the Site visit form as per attach</b> prior to tender price.</li> <li>2. Supply all labour, materials, tools, equipment, PPE and transport for the proper execution of the following works to its proper working conditions as directed and to S.O. satisfaction.</li> <li>3. Rate shall include to make good all works disturb to match or as directed by S.O and to remove debris to Contractor's own dumping Yard.</li> <li>4. No claims for additional payment will be entertained as the grounds of misunderstanding or misinterpretation of site condition, measurements etc.</li> <li>5. Contractor / vendor <b>MUST</b> be stated the brand offer and ATTACH catalog brand.</li> <li>6. Contractor / vendor <b>MUST</b> submit work programme.</li> </ol>					
<b>1.0</b>						
<b>1.1</b>	<b>MOBILIZATION, HACKING, &amp; FABRICATION WORK:</b>	Lump	Sum			
<b>1.2</b>	Mobilization of excavator machine on site.	Lump	Sum			
<b>1.3</b>	Hacking and cutting the road concrete by using cutting machine. The works shall include rectification works and make good unforeseen services pipe.	1	Lot			
<b>1.4</b>	Excavation work of Top soil with approximate measurement 1m (W) x 0.40m (D). (Approximate Length – 150m). The works shall include rectification works and make good unforeseen services pipe.	1	Lot			
<b>1.5</b>	Fabrication of form work and timber framing(W) x 0.40m (D) x 150m (L)).	1	Lot			
<b>1.6</b>	Lay PVC sheet and BRC along the trench area.  Lay Ready mix concrete G30.	Lump	Sum			
<b>2.0</b>	<b>METAL COVER:</b>					
<b>2.1</b>	Fabricate and install with heavy duty metal cover for road crossing. (Approximate measurement – 1m (W) x 9.0m (L)).	Lump	sum			
<b>2.2</b>	Fabricate and install with metal cover for field area. (Approximate measurement (W) x (L) – 1.0m x 11m –	Lump	sum			

ITEM NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT	
					\$	¢
3.0	1m x 17m – 0.75m x 23m – 0.50m x 45m – 0.30m x 37m).					
3.1	<b>NEW CHILL WATER PIPE c/w INSULATION CHEMICAL:</b>	1	Lot			
3.2	Supply, Lay and install with new pre-insulated carbon steel piping (Carbon steel pipe 6” and Carbon steel pipe 4”) including elbows, tees, reducer, and other necessary material associated with the work required. The work shall include hacking works, modification works, connection of the new CHWP with the existing system: Ensure during the by-pass connectivity of the piping system there is no disturbance of the air conditioning system inside the building as per S.O approval.	Lump	sum			
4.0						
4.1	Supply and install with new insulation chemical at the CHWP including pressure testing, flushing out and refill fresh water.	16	No			
	<b>UV-C AIR DUCT STERILIZER:</b>					
	Supply and install with new UV-C AIR DUCT STERILIZER including lamp, Ballast and mounting bracket for HVAC air germicidal Disinfection and sterilization. The work shall include wiring works 2.5mm connected to the nearest Distribution board, conduit connection, PVC pipes and new MCB.					
	(Brand: .....)					
	<b>This Package are included:</b>					
	- Restoration of defaulted ducting only works in building and thermal deep cleaning sanitization to ALL HVAC ducting system in the building.					
	- Ensure all the system running properly after the connectivity.					
	- 3 years Warranty for CHWP and trenching works including maintenance.					
	- 1-year Warranty for Ducting replacement.					
	- 5-year Warranty for UV light.					
<b>TOTAL AMOUNT</b>						

1. We offer and undertake on your acceptance of our Tender to provide the above mentioned services in accordance with your Invitation To Tender.
2. Our Tender is fully consistent with and does not contradict or derogate from anything in your Invitation To Tender. We have not qualified or changed any of the provisions of your Invitation To Tender.
3. OUR OFFER IS VALID FOR **TWELVE (12)** CALENDAR MONTHS FROM THE TENDER CLOSING DATE.
4. When requested by you, we shall extend the validity of this offer.
5. We further undertake to give you any further information which you may require.

Dated this \_\_\_\_\_ day of \_\_\_\_\_, \_\_\_\_\_.

\_\_\_\_\_  
**[Signature of authorised officer of Tenderer]**

Name:

Designation:

Tenderer's official stamp